
PLUMBING LEGEND:-	
1.	100ø SOIL & VENT PIPE
2.	100ø WASTE & VENT PIPE
2a	150ø WASTE & VENT PIPE FOR KITCHEN
2b	100ø WASTE & VENT PIPE FOR SHOP
3	75ø VENT PIPE
5	DOMESTIC DOWN TAKE
6	FLUSHING DOWN TAKE
7	65ø DOMESTIC WATER RISER PIPE
8	50ø FLUSHING WATER RISER PIPE
9	65ø SOFT WATER RISER PIPE
10	200ø RAIN WATER PIPE FOR TERRACE
11	150ø RAIN WATER PIPE FOR TERRACE
12	100ø RAIN WATER PIPE FOR TERRACE
DWS	DOMESTIC WATER SUPPLY
FWS	FLUSHING WATER SUPPLY
SWS	SOFT WATER SUPPLY
BD	BALCONY DRAIN
FT	FLOOR TRAP
⊠	150X150 CUT OUT FOR FT & WC
FD	FLOOR DRAIN
A	150ø FIRE HYDRANT RISER
B	80ø DRAIN PIPE
C	150ø FIRE SPRINKLER RISER
◪	FHC – FIRE HOSE CABINET
■	KHURRA(450X450mm)
⊠	CUTOUT 150X150mm

SURFACE PARKING AREA DIAGRAM



DETAIL OF AREA STATEMENT		
TOTAL AREA OF THE SITE (2.71875 ACRES)	=	**11002.373 SQ.MT.**
PERMISSIBLE F.A.R. (175)	=	**19254.154 SQ.MT.**
PROPOSED F.A.R. (174.92 %)	=	**19245.763 SQ.MT.**
PERMISSIBLE GROUND COVERAGE (40% OF THE SITE AREA)	=	
40 % * 7826.608 SQMT.	=	**4400.949 SQ.MT.**
PROPOSED GROUND COVERAGE (39.95 %)	=	**4320.733 SQ.MT.**

AREA STATEMENT (TO BE COUNTED IN F.A.R.)		
GROUND FLOOR AREA	=	4280.341 SQ.MT.
FIRST FLOOR AREA	=	3664.295 SQ.MT.
SECOND FLOOR AREA	=	3506.844 SQ.MT.
THIRD FLOOR AREA	=	3054.952 SQ.MT.
FOURTH FLOOR AREA	=	961.685 SQ.MT.
FIFTH FLOOR AREA	=	1260.122 SQ.MT.
SIXTH FLOOR AREA	=	1258.762 SQ.MT.
SEVENTH FLOOR AREA	=	1258.762 SQ.MT.
NET ACHIEVED F.A.R.	=	**19245.763 SQ.MT.**

BASEMENT AREA (NON F.A.R.)		
BASEMENT I AREA	=	5909.330 SQ.MT.
BASEMENT II AREA	=	5829.454 SQ.MT.
BASEMENT III AREA	=	5829.454 SQ.MT.
TOTAL BASEMENT AREA	=	**17568.238 SQ.MT.**
MUMTY & MACHINE ROOM	=	270.261 SQ.MT.
TOTAL BUILTUP AREA = FAR + NON FAR	=	**37084.262 SQ.MT.**

PARKING AREA STATEMENT		
PARKING REQUIREMENT **(1ECS FOR 50 SQ.M.) = 19253.695/50**	=	384.915
	~	**385**
REQUIRED SURFACE PARKING (15% OF THE REQUIRED PARKING)	=	221 X 15 %
	=	**58**
PROPOSED SURFACE PARKING	=	65
PROPOSED CAR PARKING at BASEMENT 1	=	122
PROPOSED CAR PARKING at BASEMENT 2	=	120
PROPOSED CAR PARKING at BASEMENT 3	=	127
TOTAL PROPOSED PARKING	=	**494**

SURFACE CAR PARKING AREA CALCULATIONS				
NO.	COEFF.	BREADTH	LENGTH	AREA (SQ.M)
DEDUCTIONS				
1	1	22.500	11.000	247.500
2	1	14.440	11.620	167.793
3	0.5	14.440	19.805	142.992
4	1	31.430	14.065	442.063
5	0.5	14.065	7.225	50.810
6	1	17.500	11.000	192.500
7	1	11.000	12.500	137.500
8	1	7.925	23.500	186.238
9	0.5	19.100	9.610	91.776
10	1	12.075	13.890	167.722
11	0.5	7.030	13.890	48.823
TOTAL DEDUCTIONS (B1)				**1875.716**
PERM. PARKING @ 25 SQMT.				**75.029**
SAYS				**75**
PROPOSED CAR PARKING				**65**

NOTES

1. YOU WILL HAVE TO BE PROVIDED THE C.F.L. AS PER THE DIRECTORS OF GOVT.
2. THE RESPONSIBILITY OF STRUCTURE DESIGN AND STRUCTURE STABILITY OF BUILDING AGAINST THE EARTHQUAKE SHALL BE ENTIRELY OF THE ARCHITECT/OWNER.
3. THE RAINWATER HARVESTING SYSTEM SHALL BE PROVIDED AS PER CENTRAL GROUND WATER AUTH. NORMS.
4. THE PROVISION OF SOLAR WATER HEATING SYSTEM SHALL BE AS PER NORMS.
5. ALL BUILDING EXCLUDING BASEMENTS FULLY AIR CONDITIONED AS PER N.B.C. NORMS & 100% POWER BACKUP.
6. ALL BUILDING ARE MECHANICALLY LIGHTED AND VENTILATED AS PER N.B.C. NORMS.
7. ALL BUILDING INCLUDING BASEMENT FULLY SPRIKLERED AS PER N.B.C. NORMS.

S.T.P. (HQ) Member Secretary B.P.C. | E.T.P. (G) Member B.P.C. | C.T.P. (HC) Chairman B.P.C.

AD | PA | ATP

Checked and found ok for Public Health (Internal) Service subject to comments if any in forwarded letter No. SE(N) Dt. 12.4.17

(BALWANT SINGH) S.D.

Superintending Engineer HUDA, Panchkula

ARCHITECTS

REVISED BUILDING PLAN OF COMMERCIAL COLONY MEASURING 2.71875 ACRES (LICENCE NO. 72 OF 2013 DATED 27.07.2013) IN SECTOR-92, GURGAON MANESAR URBAN COMPLEX BEING DEVELOPED BY M/S SPAZE TOWERS PVT. LTD.

ARCHITECTS

SACHDEVA CONSULTANTS.
Parnami Tower, 3rd Floor, S.C.O. 50-51,
Old Judicial Complex, Civil Lines,
Gurgaon – 122001
Tel.:0124-4081801,4081802
email : saccon1953@gmail.com

ARCHITECT'S SEAL & SIGNATURE	OWNER/AUTH. SIGN.
PARAMJEET SINGH ARCHITECT CA/2001/31512 Sachdeva Consultants Parnami Tower, 3rd Floor SCO 50-51, Old Judicial Complex Civil Lines, Gurgaon- 122001 (Hr.)	

Scale : **1 : 200**

Drawing Title:- **SITE PLAN**

Drawing No:- **01**